BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:-Providing drinking water facility in ward no:03

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.30, I. 9.4) PRED.SR 2008-09	Each BW	1.00	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Paise Forty Six Only
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) 29/I.1 PRED SR 2006-07 and as per corragandam SE PRED No. 9.1/2008-09	Rmtr			
	0 to 50 m		50.00	315.18	Rupees Three Hundred Fifteen and Paise Eighteen Only
	50 to 100 m		50.00	412.00	Rupees Four Hundred Twelve Only
	100 to 150 m		50.00	458.35	Rupees Four Hundred Fifty Eight and Paise Thirty Five Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	1[illegible] to 200 m		50.00	484.10	Rupees Four Hundred Eighty Four and Paise Ten Only
	200 to 250 m		50.00	560.32	Rupees Five Hundred Sixty and Paise Thirty Two Only
	250 to 350 m		50.00	600.49	Rupees Six Hundred and Paise Forty Nine Only
3	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) as per corragandam SE PRED No. 2/2012-13	Rmtr	80.00	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
4	Providing 250mm dia PVC Pipe 6kg/cm as per specification and direction of the Engineer in Charge of the work	Rmtr	25.00	1133.00	Rupees One Thousand One Hundred Thirty Three Only
5	Providing and fixing 175mm Borewell Cap PRED SR 2012-13 Page Nio SL.No	No.	1.00	100.00	Rupees One Hundred Only
6	Providing and fixing of clampset and borewell cap to the pump.	No.	1.00	450.00	Rupees Four Hundred Fifty Only
7	Providing and 175mm dia MS Coler etc as per specification and direction engineer in charge of the work.	NO,S	15.00	150.00	Rupees One Hundred Fifty Only
8	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 15.00 HP 30 stage.(P.NOXXXX1 S.NO.34 of PWD SR for 2015-16) 12.5 HP 20 Stage	No	1.00	70600.00	Rupees Seventy Thousand Six Hundred Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
9	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008. 50 mm dia including Collar Heavy Class 2015-16, P-90, i.no13.15	Rmtr	275.00	431.00	Rupees Four Hundred Thirty One Only
10	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 46/ I No. 30-B 4.0 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2007-08 3/2008-09 4538/19.01.2009 (1x3x6.00 Sqmm PVC cable)	Mtr	290.00	188.70	Rupees One Hundred Eighty Eight and Paise Seventy Only
11	Heavyduty coller 50mm dia	Nos	15.00	150.00	Rupees One Hundred Fifty Only
12	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09	No	1.00	3000.00	Rupees Three Thousand Only
13	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 51/ I No.6.66 /f KPWD Electrical SR 2014-2015	No.	1.00	302.00	Rupees Three Hundred Two Only
14	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class. 4 core 16 Sqmm(confirming to IS 1554)P.NO(-553,s.no-10(d)bwssb sr(13-14)	Mtr	30.00	169.95	Rupees One Hundred Sixty Nine and Paise Ninety Five Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
15	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P-68 /I.No.7.8.1a) KPWD Electrical SR 2014-2015	Mtr	40.00	10.80	Rupees Ten and Paise Eighty Only
16	Digging or trenching of 0.6 m x 0.5 m wide refilling the trench to the required ground level and consolidating etc., complete as per Civil SR KSRB 1-2 P-7 P No. 68/ I. No. 7.93 KPWD Electrical SR 2014-2015	Mtr	25.00	85.00	Rupees Eighty Five Only
17	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 69/ I No.15-A KPWD Electrical SR 2014-2015	Mtr	4.00	345.00	Rupees Three Hundred Forty Five Only
18	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 69/ I No. 7.132 KPWD Electrical SR 2014-2015	No.	1.00	280.00	Rupees Two Hundred Eighty Only
19	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, (PWD Electrical SR-1999-2000, P-62, I.No.7) KPWD Electrical SR 2014-2015	No	1.00	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
20	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 52/I No 6.73 KPWD Electrical SR 2014-2015 63 Amps	No.	3.00	234.00	Rupees Two Hundred Thirty Four Only
21	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13-7.1-4 P.No. 9/I No. 13.55 PWD SR 2015-2016	No	1.00	1579.40	Rupees One Thousand Five Hundred Seventy Nine and Paise Forty Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
22	Providing NP/CP waste uniona conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 95/ I. No. 13.81.3 PWD SR 2015-2016	No	1.00	227.90	Rupees Two Hundred Twenty Seven and Paise Ninety Only
23	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc coomplete(p.noxxxv11 pwd sr-2015-2016)	No	4.00	104.30	Rupees One Hundred Four and Paise Thirty Only
24	Supplying shunt trip capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications(p.no54 S.NO6.13 KPWD SR 2013-2014)	No	1.00	1486.00	Rupees One Thousand Four Hundred Eighty Six Only
25	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications GROUP A (P.NO6.15.9/P.NO-54 ELE SR2014-2015)	No	1.00	1547.00	Rupees One Thousand Five Hundred Forty Seven Only
26	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.35 P.No. 57 I. No.6.41 .20 KPWD Electrical SR 2014-2015	Sq.Cm	23400.00	0.34	Rupees and Paise Thirty Four Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
27	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shinea/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. 15HP to 30 HP Star Delta Starter SERDED Rate	No.	1.00	11000.00	Rupees Eleven Thousand Only
28	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2018-2019	Cum	292.50	161.71	Rupees One Hundred Sixty One and Paise Seventy One Only
29	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.3 item No.4.2 PRE	Rmtr	390.00	475.94	Rupees Four Hundred Seventy Five and Paise Ninety Four Only
30	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, No. 6/ Item No. 2.11/ PWD SR 2018-2019	Cum	292.50	128.26	Rupees One Hundred Twenty Eight and Paise Twenty Six Only
31	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3/P 89/I 13.37 PWD SR -2018-2019)	Each	8.00	1843.34	Rupees One Thousand Eight Hundred Forty Three and Paise Thirty Four Only

EXECUTIVE ENGINEER-4
Signature of Contractor
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,